

Original VELUX flashings for reliable installation

Flashing: EDW 0000



New Generation
novation
ouvelle




For profiled roofing material up to 120 mm

- A perfect match with VELUX roof window
- Fast installation
- Maintenance-free and no corrosion
- Apron in unique, lacquered sandwich construction
- Tested for extreme weather conditions
- VELUX guarantee

Flashing EDW 0000 features



Flashing material:
Aluminium
Dark grey



Apron material:
Aluminum and
bitumen
sandwich
construction.
Dark grey.




Roof pitch:
15°-90°



Profile height:
max 120 mm
















Side section:
Foam height
75 mm




Standard
installation:
Red line level

Single and combi-flashings


Profiled roofing material: 120 mm		
1		EDW
2		EBW
3		EKW
4		EKW ---7- + EDW
5		EFW
6		EFW --22/32
7		EDW (available from 2015)
8		ETW + EDW
9		ETW + ETW --00- + EKW
10		EKX --88
11		EEW + EEX
12		EAW
13		EUW 0001/2/3

Technical drawing




Technical specifications

Material:	Aluminium alloys
Aluminum thickness:	0,47 mm - 0,70 mm
Coating thick:	Min 24 µm, according to EN 13523-1
Gloss 60°:	30E, according to EN 13523-2
Standard color:	Grey NCS S 7500-N, according to EN 13523-3
Foam:	Profile 75 mm high, polyurethane with fine cell structure



Available flashing materials



Aluminium, Dark grey


Aluminium, Black

Zink

Copper

Aluminum any colour

Available apron materials



Dark grey

Yellow ochre

Red terracotta

Black

Any colour

Benefits



Reliable and fast installation

A perfect match - designed to fit the window precisely. Convenient, reliable, fast and easy installation. Saves time and money – and gives you satisfied customers.



Tested for extreme weather conditions

The VELUX flashings have been tested in our wind tunnel – the largest in Northern Europe. Your guarantee for a reliable and durable product.



Discreet and attractive design

The VELUX flashing design has been proven on millions of roofs world-wide. Pleasing aesthetics, no corrosion, and totally maintenance-free. The wellknown VELUX quality you can trust.



Original



Fast & easy to install



Perfect fit



Weather proof



Warranty

VELUX®

Contact:
VELUX Denmark A/S
Breltevej xx
2970 Hørsholm
Support: 2323 4545